


SCREENING SITE INSPECTION WORK PLAN
FOR

LOGAN STORAGE SITES
FRANKLIN GROVE, ILLINOIS
U.S. EPA ID: ILD025475914
SS ID: N/A
TDD: F05-8917-089
PAN: FILO705SA



MARCH 8, 1990

Elements of this Screening Site Inspection Work Plan are considered confidential and pre-decisional in nature. Material and information contained within this report may not be released without the approval of the United States Environmental Protection Agency Region V Pre-Remedial Unit.



ecology and environment, inc.

111 WEST JACKSON BLVD., CHICAGO, ILLINOIS 60604, TEL. 312-663-9415

International Specialists in the Environment

recycled paper



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 5

230 SOUTH DEARBORN ST.

CHICAGO, ILLINOIS 60604

REPLY TO THE ATTENTION OF:

5HR-11

Mr. Thomas Crause, Manager
Hazardous Substances Planning Unit
Illinois Environmental
Protection Agency
2200 Churchill Rd.
Springfield, Illinois 62794-9276

Site Name: Logan Storage Sites

Location: Franklin Grove

Identification No. ILD025475914

Date: March 8 1990

Dear Mr. Crause:

Attached is a copy of the site inspection work plan which has been prepared for the site listed above. This document is considered to be draft and subject to changes and modifications based on actual conditions which may be encountered at the site.

Because this is considered to be a draft document, it should be for official use only and should not be distributed outside of your agency without prior notification and approval of the U.S. Environmental Protection Agency.

The document also contains a preliminary estimate of the Hazard Ranking System (HRS) score for the site and a project score based on specific assumptions as addressed in the work plan. This information is considered predecisional. Therefore, it should not be released. Your field and district staff especially should be made aware of the predecisional nature of this score, the legal implications of releasing it relative to the National Priorities List (NPL) candidacy process, and therefore the need not to release any score. If you have any questions concerning release of this information, please contact Ms. Jeanne Griffin, of my staff, at (312) 886-3007.

If you have any comments on the work plan itself, please contact Mr. Charles Castle, of my staff, at (312) 886-5892, within eight calendar days. If we do not receive any comments written or verbal from you, then we will assume that the work plan is acceptable.

Please note that inspections are carried out under CERCLA to determine if a site will make the NPL. Thus, extra sampling or other activities that serve only a State purpose should not be requested. We will welcome suggestions based on the knowledge of you and your staff that will make for a better site inspection for NPL candidacy purpose.

Please talk with Mr. Castle as early within the comment period as possible in order that your suggestions can be evaluated and modifications made.

Sincerely yours,

A handwritten signature in cursive script that reads "Thomas Geishecker".

Thomas Geishecker, Chief
Technical Support Section

Enclosures

1427:4

WORK PLAN	1
-----------	----------

SITE MAPS	2
-----------	----------

HRS WORKSHEETS	3
----------------	----------

APPENDIX	4
----------	----------

REFERENCES	5
------------	----------

WORK PLAN

INSPECTION WORK PLAN

THIS DOCUMENT IS CONFIDENTIAL. Due to the predecisional nature of this document, this document and its attachments are not to be released without prior approval of the United States Environmental Protection Agency (U.S. EPA).

This site inspection work plan (WP) has been prepared by Ecology and Environment, Inc., or its subcontractor, C. C. Johnson and Malhotra, P.C., under the field investigation team (FIT) contract with U.S. EPA (No. 68-01-7347).

The objectives of this WP are to:

- o Prepare a preliminary Hazard Ranking System (HRS) score using HRS 1 (40 CFR 300, July 16, 1982) criteria based on existing file information (Part C of WP);
- o Prepare projected HRS 1 scores based on experience and professional judgement (Part C of WP);
- o Identify HRS 1 score data gaps (Part E of WP); and
- o Propose site inspection activities to satisfy the HRS 1 score data gaps; technical approach and estimated LOE are provided (Parts E and I, respectively).

Unless otherwise stated, QA/QC protocol for site inspection activities is documented in the Quality Assurance Project Plan Region V FIT Conducted Site Inspections - May 1, 1987.

A. GENERAL INFORMATION

CERCLIS SITE NAME: Logan Storage Site
ALSO KNOWN AS: Bob Logan Tractor Company
FORMERLY KNOWN AS: N/A
ADDRESS: Box 216, State Street
CITY: Franklin Grove
STATE: Illinois
COUNTY: Lee
ZIP CODE: 61031
U.S. EPA ID: ILD025475914
SSID: N/A
TDD: FO5-8912-089
PAN: FIL07055A

FIT USE ONLY

WORK PLAN TYPE: ☒ SCREENING SITE INSPECTION (SSI) WORK PLAN

OTHER: _____

PREPARED BY: Jeff Taylor (FIT)

DATE: 2/5/90

REVIEWED BY: Karen M. Sparger (FIT)

DATE: February 13, 1990

APPROVED BY: Regina Guyer (FIT)

DATE: 3/5/90

U.S. EPA USE ONLY

REVIEWED BY: _____ (U.S. EPA) DATE: _____

___ WORK PLAN APPROVED. Recommend issuance of TDD to implement the Work Plan.

___ WORK PLAN APPROVED. No Further Remedial Action Planned (NFRAP).

___ WORK PLAN REJECTED.

COMMENTS: _____

B. SITE INFORMATION

This section of the WP presents current and historic information pertaining to the site, including: site operations, storage/disposal methods, site property area, site status, owners and operators, permit information, and response/enforcement activities. A site location map is shown on Figure 1, located in Section 2.

1. Site Operations (past and present; check all that apply):

<input checked="" type="checkbox"/> Above ground storage	<input type="checkbox"/> Mining site
<input type="checkbox"/> Below ground storage	<input type="checkbox"/> Open dump
<input type="checkbox"/> Chemical manufacturer	<input type="checkbox"/> Ore processor
<input type="checkbox"/> Drum recycler	<input type="checkbox"/> Physical/chemical treatment
<input type="checkbox"/> Electroplater	<input type="checkbox"/> Recycler/reclaimer
<input type="checkbox"/> Foundry	<input type="checkbox"/> Surface impoundment
<input type="checkbox"/> Incinerator	<input type="checkbox"/> Underground injection
<input type="checkbox"/> Landfarm	<input type="checkbox"/> Well field
<input type="checkbox"/> Landfill	<input type="checkbox"/> Wood preserver
<input type="checkbox"/> Midnight dump	<input checked="" type="checkbox"/> Other: <u>Used Tractor Part</u>
	<u>Scrap</u>

References: 1 , 9 , _____ , _____ , _____

2. Storage/Disposal Methods (past and present; check all that apply):

Waste Quantity
(amount/units of measure)

<input checked="" type="checkbox"/> Drums, above ground	<u>~ 1400</u>
<input type="checkbox"/> Landfarm	_____
<input type="checkbox"/> Landfill	_____
<input type="checkbox"/> Open dump	_____
<input type="checkbox"/> Piles	_____
<input type="checkbox"/> Surface impoundment	_____
<input type="checkbox"/> Tank, above ground	_____
<input type="checkbox"/> Tank, below ground	_____
<input type="checkbox"/> Other: _____	_____

References: 1 , 9 , _____ , _____ , _____

3. Site Property Area: ~2 (acres)

References: 1 , 2 , _____ , _____ , _____

4. Site History/Description and Unusual Features: (see following page.)

References: 1 , 9 , 10 , 11 , _____

SITE HISTORY (Continued)

During the mid 1970's Mr Bob Logan began storing drums of Paint sludge and paint waste solvents at his place of business in Franklin Grove, Illinois. This waste originated from the Valspar Corporation of Rockford, Illinois. By 1976, Mr Logan had accreted approximately 1400 drums of this paint waste. On May 29, 1980 the Illinois Environmental Protection Agency (IEPA) conducted a site investigation and observed drums on this site. Another site investigation by the IEPA on June 25 1980, discovered that some drums were leaking. According to Mr. Logan he was in the process of getting rid of the drums. Over the next two years the IEPA conducted numerous site investigations and observed that the drums were being removed. File information indicates that the drums were sent to various locations, some to BFI/Davis Junction IL. landfill, some to Huckill Chemical and Solvent Recovery Corporation, and others to a Landfill in North Dakota. File information also indicates that by October 30 1982 the drums had been removed along with any spilled material and contaminated soil. According to the IEPA Regional office that there was a report that drums were alleged to have been buried on site.

5. Site Status: ☒ Active _____ Inactive

References: 1 , _____ , _____ , _____ , _____

6. Owner/Operator History

Current Owner

Name: Robert Logan
Address: Box 216 State Street

City, State, Zip Code: _____
Franklin Grove, IL 61031
Years of Ownership: > 40 yrs

Current Operator

Name: Robert Logan
Address: Box 216 State Street

City, State, Zip Code: _____
Franklin Grove, IL 61031
Type of Operation: Farm implement Sales/Drum Storage
Years of Operation: Unknown

Previous owners

(list most recent first)

Name: N/A
Address: _____

City, State, Zip Code: _____

Years of Ownership: _____

Name: N/A
Address: _____

City, State, Zip Code: _____

Years of Ownership: _____

Previous operators

(list most recent first)

Name: N/A
Address: _____

City, State, Zip Code: _____

Type of Operation: _____

Years of Operation: _____

Name: N/A
Address: _____

City, State, Zip Code: _____

Type of Operation: _____

Years of Operation: _____

References: 1 , 12 , _____ , _____ , _____

7. Permit Information

Effective Date

Expiration Date

<u>NPDES</u>	_____	_____
<u>UIC</u>	_____	_____
<u>AIR</u>	_____	_____
<u>RCRA, PART A PART B</u>	_____	_____
<u>SPCC PLAN</u>	_____	_____
<u>STATE (specify):</u>	_____	_____
<u>LOCAL (specify):</u>	_____	_____
<u>OTHER (specify):</u>	_____	_____
<input checked="" type="checkbox"/> <u>NONE</u>	_____	_____

References: 1 , _____ , _____ , _____ , _____

8. Response Activities (previous and current site remediation; check all that apply):

- | | |
|---|--|
| <input type="checkbox"/> Water supply closed | <input type="checkbox"/> Cutoff trenches/sump |
| <input type="checkbox"/> Temporary water supply provided | <input type="checkbox"/> Subsurface cutoff wall |
| <input type="checkbox"/> Permanent water supply provided | <input type="checkbox"/> Barrier wall constructed |
| <input checked="" type="checkbox"/> Spilled material removed | <input type="checkbox"/> Capping/covering |
| <input checked="" type="checkbox"/> Contaminated soil removed | <input type="checkbox"/> Bulk tankage repaired |
| <input type="checkbox"/> Waste repackaged | <input type="checkbox"/> Grout curtain constructed |
| <input checked="" type="checkbox"/> Waste disposed elsewhere | <input type="checkbox"/> Bottom sealed |
| <input type="checkbox"/> On-site burial | <input type="checkbox"/> Gas control |
| <input type="checkbox"/> In situ treatment | <input type="checkbox"/> Fire control |
| <input type="checkbox"/> Encapsulation | <input type="checkbox"/> Leachate treatment |
| <input type="checkbox"/> Emergency waste treatment | <input type="checkbox"/> Area evacuated |
| <input type="checkbox"/> Cutoff walls | <input type="checkbox"/> Access to site restricted |
| <input type="checkbox"/> Emergency diking/surface water diversion | <input type="checkbox"/> Population relocated |

Other remedial and enforcement activities: File information
indicates the drums were removed. Some were sent to
land fills and others were sent to chemical recyclers. File
information also indicates Mr Logan began his possession
his own and the IEPA monitored the situation's progress.

References: 1 , 9 , _____ , _____ , _____

9. Documented and Alleged Target Compounds

Documented and alleged target compounds are compiled in Table 1. The documented target compounds are supported by analytical data from previous sampling projects. The alleged target compounds are based on the history of site operations and professional judgement. Documented and alleged target compound locations are shown on Figure 2, located in Section 2.

[illegible]

Table i

DOCUMENTED/ALLEGED TARGET COMPOUND LIST

C. PRELIMINARY/PROJECTED HRS SCORES

The purpose of this section is to:

- o Prepare a preliminary HRS 1 score based on existing file information; and
- o Prepare projected HRS 1 scores based on experience and professional judgement.

PRELIMINARY HRS SCORE (this score is based on existing file information that was obtained prior to the screening site inspection):

$$S_M = \underline{0} \quad S_{FE} = \underline{0} \quad S_{DC} = \underline{0}$$

PROJECTED HRS SCORE FOR A SCREENING SITE INSPECTION (this score is based on the expected acquisition of information from the screening site inspection):

$$S_M = \underline{24.42} \quad S_{FE} = \underline{0} \quad S_{DC} = \underline{16.67}$$

PROJECTED HRS SCORE FOR A LISTING SITE INSPECTION (this score is based on the expected acquisition of information from the Listing Site Inspection):

$$S_M = \underline{40.70} \quad S_{FE} = \underline{0} \quad S_{DC} = \underline{16.67}$$

HRS 1 score worksheets are located in Section 3.

D. WORK SUMMARY

Based on the preliminary and projected HRS scores, a site inspection will be performed.

The objectives of the site inspection are to:

- o Provide information to satisfy HRS data gaps;
- o Develop the information base needed to permit U.S. EPA to evaluate the need for future site activities; including: immediate removal measures, additional investigation, or no further action; and
- o Characterize hazardous substances, pollutant dispersal pathways, types of receptors, facility management practices, and potentially responsible parties.

Specific tasks to be conducted during the site inspection are (check all that apply):

- ☒ Interview site owner(s)/representative(s)
- ☒ Take photographs of site and surrounding areas
- ☒ Screen site with safety instrumentation (i.e., HNU, OVA, O₂ meter, explosimeter, radiation detector, cyanide detector)
- ☒ Collect environmental samples
- ☒ Assess the need for Immediate Removal Actions
- ☐ FASP*
- ☐ Soil gas monitoring*
- ☐ Well point installations*
- ☒ Geophysics*: OYO model-2441 Geo radar - I Grand (Specify)
- ☐ OTHER*: Penetrating Radar Unit, E6+6 Geomatrix Pro-
cession magnetometer.

* Rationale for these activities and their impact on HRS data gaps:

These techniques will be used in an attempt to
verify a report of alleged buried drums.

E. PROPOSED SAMPLE PLAN

The HRS data gaps are identified in this section, and a proposed sample plan is developed based on the type of information required.

1. A) HRS data gap(s): Waste characteristics

B) Sampling proposed to satisfy HRS data gap(s):

☒ Soil ☐ Sediment ☐ GW ☐ SW ☐ Air ☐ Waste

C) Sampling procedures (number and types of samples; equipment; methodology): Five Soil samples are proposed for this data gap, including 4 on-site subsurface soil samples and one off-site sample for potential background characteristics. All samples will be picked and shipped as per proper EPA and ETE protocol.

A table of proposed sample descriptions is presented in Table 2, Section 1. A proposed sample location map is presented on Figure 3 in Section 2.

2. A) HRS data gap(s): Observed release to groundwater

B) Sampling proposed to satisfy HRS data gap(s):

☐ Soil ☐ Sediment ☐ GW ☐ SW ☐ Air ☐ Waste

C) Sampling procedures (number and types of samples; equipment; methodology): No samples are proposed for this data gap. Residential and municipal wells are located greater than 1/4 mile from the site.

A table of proposed sample descriptions is presented in Table 2, Section 1. A proposed sample location map is presented in Figure 3, in Section 2.

Note: Sample locations and/or the number of samples may be changed or eliminated at the discretion of the site team leader in response to actual site conditions during the course of the inspection.

E. PROPOSED SAMPLE PLAN

The HRS data gaps are identified in this section, and a proposed sample plan is developed based on the type of information required.

3. A) HRS data gap(s): Observed release to surface water

B) Sampling proposed to satisfy HRS data gap(s):

 Soil Sediment GW SW Air Waste

C) Sampling procedures (number and types of samples; equipment; methodology): No Samples are proposed for this data gap, since an overland route is not believed to exist.

A table of proposed sample descriptions is presented in Table 2, Section 1. A proposed sample location map is presented on Figure 3 in Section 2.

4. A) HRS data gap(s): Fire and Explosion, Direct Contact, Air Route

B) Sampling proposed to satisfy HRS data gap(s):

 Soil Sediment GW SW Air Waste

C) Sampling procedures (number and types of samples; equipment; methodology): These data gaps will be addressed during the site representative interview.

A table of proposed sample descriptions is presented in Table 2, Section 1. A proposed sample location map is presented in Figure 3, in Section 2.

Note: Sample locations and/or the number of samples may be changed or eliminated at the discretion of the site team leader in response to actual site conditions during the course of the inspection.

Table 2
PROPOSED SAMPLE DESCRIPTIONS
(INCLUDING ALL LABORATORY BLANKS AND DUPLICATES)

F. COMMENTS

It is believed Mr Logan still operates his used Tractor parts company on this site, but it is believed he no longer accepts drums of waste.

In a Telephone Conversation w/ Bob Wengrow of the IEEO, FIT was informed that no enforcement activities were even enacted at this site. He also told FIT of a report of alleged buried drums.

G. HEALTH AND SAFETY

Proposed E & E Health and Safety protocol to be followed during site inspection.

1. Anticipated level of protection: A B C ✓ D
2. Level of protection modifications: Level D, with possible upgrades to level C if monitoring equipment action levels are reached.
3. Work limitations (time of day, etc.): Work will be limited to day light hours only. Team members will be monitored for heat/cold stress. The buddy system will be observed at all times when on site.

H. TYPE OF DELIVERABLE

Proposed report format to be submitted to U.S. EPA.


1. ✓ SSI Report including U.S. EPA 2070-13 Form
2. Letter Report
3. Other

SUBTASK CODE	SUBTASK																					
	General Non-Specific	File Search/Review	Work Plan	Safety Plan	QAPP	Mobilization/Demobilization	Travel	Non-Sampling Field Work	Sample Management	Field Sampling	Screening / Analytical	Subcontract	Meteorologic / Air Sampling Studies	Geophysical Work	Hydrogeological Work	Data Processing/Modeling	Data Validation	Draft Final Deliverable	Internal QA Review	Final Deliverable	Respond To Comments	
	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	TOTAL
TEAM LEADER	12	12		8		4	8	8		8				8				60		20	8	156
SAFETY OFFICER	2			1		4	8	8		8				8								39
SAMPLER	2					2	8	8	16					8								44
TEAM MEMBER	2					2	8	8		8				8								36
TEAM MEMBER	2					2	8	8		8				8								36
Publications																			40			40
Sample Coord.									4													4
Audit Team	1																		25			25
QA/Admin				8													5					13
TOTALS FOR PROJECT	20	12		17		14	40	40	20	32				40			5	60	65	20	8	400

I. ESTIMATED LOE HOURS

SUMMARY OF PROJECTED HOURS NEEDED TO IMPLEMENT
SITE INSPECTION AND COMPLETE SITE INSPECTION REPORT.

SITE MAPS



ecology and environment, inc.

111 WEST JACKSON BLVD., CHICAGO, ILLINOIS 60604, TEL. 312-663-9415

TITLE SITE LOCATION MAP		FIGURE # 1
SITE LOGAN STORAGE SITE		SCALE 1:24000
CITY FRANKLIN GROVE	STATE IL	P.A.N. FIL0705SA
SOURCE USGS TOPOGRAPHIC MAP FRANKLIN GROVE IL		DATE 1983
		REVISED

RT 38

DRUM STORAGE AREA

ACCESS RD


OFFICE

ecology and environment, inc.

111 WEST JACKSON BLVD., CHICAGO, ILLINOIS 60604, TEL. 312-663-8418


TITLE SITE FEATURES MAP		FIGURE # 2
SITE LOGAN STORAGE SITE		SCALE NOT TO SCALE
CITY FRANKLIN GROVE	STATE IL	P.A.N. FIL0705SA
SOURCE IEPA MEMO/MAP 4/15/81 BY P.D. LOPINTO		DATE REVISED

RT 38



ACCESS RD

OFFICE



ALLEGED AREA
OF CONTAMINATION

(A)


LETTERED ITEMS
CORRESPOND TO
TABLE 1

ecology and environment, inc.

111 WEST JACKSON BLVD., CHICAGO, ILLINOIS 60604, TEL. 312-663-9416

TITLE DOCUMENTED/ALLEGED TARGET COMPOUND MAP		FIGURE # 3
SITE LOGAN STORAGE SITE		SCALE NOT TO SCALE
CITY FRANKLIN GROVE	STATE IL	P.A.N. FIL0705SA
SOURCE IEPA MEMO/MAP 4/15/81 BY P.D. LOPINTO		DATE
		REVISED

RT 38



ACCESS RD

OFFICE

▲ S5

POTENTIAL BACKGROUND SAMPLE

▲ PROPOSED SOIL SAMPLE LOCATION

ecology and environment, inc. 111 WEST JACKSON BLVD., CHICAGO, ILLINOIS 60604, TEL 312-863-9415		
TITLE PROPOSED SOIL SAMPLE LOCATION MAP		FIGURE # 4
SITE LOGAN STORAGE SITE		SCALE NOT TO SCALE
CITY FRANKLIN GROVE	STATE IL	P.A.N. FIL0705SA
SOURCE IEPA MEMO/MAP 4/15/81 BY P.D. LOPINTO		DATE REVISED

Hazard Ranking System 1
Score Worksheets

PRELIMINARY AND PROJECTED
HAZARD RANKING SYSTEM
SCORE WORKSHEETS

Site Name: Logan Storage Sites (Cerdis Name)
Bob Logan Tractor Company (AKA)
Address: Box 216 State Street
City/County/State/Zip Franklin Grove, Lee, Illinois, 61031
Cerdis ID # ILD 025475914 SSID None
Prepared by Jeff Taylor E&E Date 2/5/90
Reviewed by Karen M. Jorgensen E&E Date February 13, 1990
TDD: F05-8912-089 PAN FIL07055A

Type of Document

PA
PA Reassessment
WP-SSI ✓
WP-LSI

PRELIMINARY HRS SCORE

$S_M =$ 0 $S_{FE} =$ 0 $S_{OC} =$ 0

PROJECTED HRS SCORE FOR SCREENING SITE INSPECTION (SSI)


$S_M =$ 24.42 $S_{FE} =$ 0 $S_{OC} =$ 16.67

PROJECTED HRS SCORE FOR LISTING SITE INSPECTION (LSI)

$S_M =$ 40.70 $S_{FE} =$ 0 $S_{OC} =$ 16.67


PRELIMINARY HRS SCORE

(THIS SCORE IS BASED ON EXISTING FILE INFORMATION THAT WAS OBTAINED PRIOR TO THE SCREENING SITE INSPECTIONS)

	S	S'
Groundwater Route Score (S_{gw})	0	0
Surface Water Route Score (S_{sw})	0	0
Air Route Score (S_A)	0	0
$S_{gw}^2 + S_{sw}^2 + S_A^2$		0
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_A^2}$		0
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_A^2} / 173 - S_M$		0


PROJECTED HRS SCORE FOR SCREENING SITE INSPECTION (SSI)

(THIS SCORE IS BASED ON THE EXPECTED ACQUISITION OF INFORMATION FROM THE SCREENING SITE INSPECTIONS)

	S	S'
Groundwater Route Score (S_{gw})	42.24	1784.22
Surface Water Route Score (S_{sw})	0	0
Air Route Score (S_A)	0	0
$S_{gw}^2 + S_{sw}^2 + S_A^2$		1784.22
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_A^2}$		42.24
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_A^2} / 173 - S_M$		24.42

PROJECTED HRS SCORE FOR LISTING SITE INSPECTION (LSI)

(THIS SCORE IS BASED ON THE EXPECTED ACQUISITION OF INFORMATION FROM THE LISTING SITE INSPECTIONS)

	S	S'
Groundwater Route Score (S_{gw})	70.41	4957.57
Surface Water Route Score (S_{sw})	0	0
Air Route Score (S_A)	0	0
$S_{gw}^2 + S_{sw}^2 + S_A^2$		4957.57
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_A^2}$		70.41
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_A^2} / 173 - S_M$		40.70

GROUNDWATER ROUTE

PRELIMINARY HRS SCORE WORKSHEET					
(This score is based on existing file information that was obtained prior to the Screening Site Inspection.)					
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #
1 Observed Release	0 45	x1		No Documentation	-
If Observed Release scores 45 proceed to line 4 If Observed Release scores 0 proceed to line 2					
2 Route Characteristics				Aquifer Description:	
				Sandstone	3
				Limestone	
Depth to Aquifer of concern	0 1 2 3	x2	4	40 ft	3
Net Precipitation	0 1 2 3	x1	1	Precip 34" Evap 32"	4
Permeability of the Unsaturated Zone	0 1 2 3	x1	1	10^{-5} - 10^{-7} cm/sec	3
Physical State	0 1 2 3	x1	0	Unknown	-
Total Route Char. Score			6		
3 Containment	0 1 2 3	x1	3	Drums leaking	10
4 Waste Characteristics					
Persistence	0 1 2 3				
Toxicity	0 1 2 3				
Haz. Waste Quantity	0 1 2 3 4 5 6 7 8	x1	0	Unknown	-
Total Waste Char. Score			0		
5 Targets					
Groundwater Use	0 1 2 3	x3	9	Drinking water	8
Distance to Nearest Well	0 1 2 3 4			~ 1/4 mile	8, 2
Population Served	0 1 2 3 4 5	x1	30	~ 1274 people	8, 2
Total Targets Score			39		
6 If line 1 is 45, multiply 1 x 4 x 5					
If line 1 is 0, multiply 2 x 3 x 4 x 5			0		
7 Divide line 6 by 57,330 and multiply by 100			S _{gw} = 0		

GROUNDWATER ROUTE

PROJECTED HRS SCORE WORKSHEET FOR SCREENING SITE INSPECTION (SSDI)					
(This score is based on the expected acquisition of information from the Screening Site Inspection.)					
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #
1 Observed Release	0 45	x1	0	No documentation	-
If Observed Release scores 45 proceed to End 4 If Observed Release scores 0 proceed to End 2					
2 Route Characteristics				Aquifer Description: Sandstone Limestone	3
Depth to Aquifer of concern	0 1 2 3	x2	4	40 ft	3
Net Precipitation	0 1 2 3	x1	1	Precip 34 Evap 32	4
Permeability of the Unsaturated Zone	0 1 2 3	x1	1	10^{-5} to 10^{-7} cm/sec	3
Physical State	0 1 2 3	x1	3	Paints Liquids, Sludges	1
Total Route Char. Score			9		
3 Containment	0 1 2 3	x1	3	Barrels leaking	1, 10
4 Waste Characteristics					
Persistence	0 1 2 3			Assume heavy metals,	
Toxicity	0 1 2 3 4 1 3 6 9 12 2 6 9 12 15 3 9 12 15 18	x1	18	(Lead) From Paint Sludges	1
Haz. Waste Quantity	0 1 2 3 4 5 6 7 8	x1	5	~ 1400 drums	1, 10
Total Waste Char. Score			23		
5 Targets					
Groundwater Use	0 1 2 3	x3	9	Drinking water	8
Distance to Nearest Well	0 1 2 3 4 0 0 0 0 0 1 0 4 6 8 10 2 0 8 12 16 20 3 0 12 18 24 30 4 0 16 24 32 35 5 0 20 30 35 40			~ 1/4 mile to well	8, 2
Population Served	0 1 2 3 4 5	x1	30	~ 1274 people	8, 2
Total Targets Score			39		
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			24219		
7 Divide line 6 by 57,330 and multiply by 100			$S_{gw} = 42.24$		

GROUNDWATER ROUTE

PROJECTED HRS SCORE WORKSHEET FOR LISTING SITE INSPECTION (LSI)					
(This score is based on the expected acquisition of information from the Listing Site Inspection.)					
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #
1 Observed Release	0 (45)	x1	45	Assume observed release	
If Observed Release scores 45 proceed to line 4 If Observed Release scores 0 proceed to line 2					
2 Route Characteristics				Aquifer Description:	
Depth to Aquifer of concern	0 1 2 3	x2		ft.	
Net Precipitation	0 1 2 3	x1		Precip Evap	
Permeability of the Unsaturated Zone	0 1 2 3	x1		cm/sec	
Physical State	0 1 2 3	x1			
Total Route Char. Score					
3 Containment	0 1 2 3	x1			
4 Waste Characteristics				Assume heavy metals, (Lead) from Paint Sedges	
Persistence	0 1 2 (3)				
Toxicity	0 0 0 0 0 1 3 6 9 12 2 6 9 12 15 (3) 9 12 15 (18)	x1	18		
Haz. Waste Quantity	0 1 2 3 4 (5) 6 7 8	x1	5	~ 1400 drums	1, 10
Total Waste Char. Score			23		
5 Targets					
Groundwater Use	0 1 2 (3)	x3	9	Drinking Water	8
Distance to Nearest Well	0 0 0 0 0 0 4 6 8 10 1 8 12 16 20 (3) 0 12 18 24 (30) 4 0 16 24 32 35 5 0 20 30 35 40			~ 1/4 mile	8, 2
Population Served	(3)	x1	30	~ 1274 people	8, 2
Total Targets Score			39		
If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			40365		
7 Divide line 6 by 57,330 and multiply by 100			S _{gw} = 70.41		

SURFACE WATER ROUTE

PRELIMINARY HRS SCORE WORKSHEET

(This score is based on existing file information that was obtained prior to the Screening Site Inspection.)

Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #																														
1 Observed Release	0 45	x1	0	No documentation																															
If Observed Release scores 45 proceed to line 4 If Observed Release scores 0 proceed to line 2																																			
2 Route Characteristics				Facility 3 %	2																														
	Intervening Terrain	x1	0	Interv 3 %	2																														
	<table style="font-size: small;"> <tr><td>Facility</td><td>0</td><td>1</td><td>2</td><td>3</td></tr> <tr><td>Slope</td><td>0</td><td>1</td><td>2</td><td>3</td></tr> <tr><td></td><td>0</td><td>2</td><td>2</td><td>3</td></tr> <tr><td></td><td>0</td><td>2</td><td>3</td><td>3</td></tr> </table>	Facility	0	1	2	3	Slope	0	1	2	3		0	2	2	3		0	2	3	3														
Facility	0	1	2	3																															
Slope	0	1	2	3																															
	0	2	2	3																															
	0	2	3	3																															
1-yr. 24 hr. Rainfall	0 1 2 3	x1	2	2.5 in.	5																														
Distance to Nearest Surface Water	0 1 2 3	x2	4	~1/4 mi. to Franklin Cr.	2																														
Physical State	0 1 2 3	x1	0	Unknown	-																														
Total Route Char. Score			6																																
3 Containment	0 1 2 3	x1	3	Drums leaking	10																														
4 Waste Characteristics																																			
Persistence	0 1 2 3			Unknown	-																														
Toxicity	<table style="font-size: small;"> <tr><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>1</td><td>3</td><td>6</td><td>9</td><td>12</td></tr> <tr><td>2</td><td>6</td><td>9</td><td>12</td><td>15</td></tr> <tr><td>3</td><td>9</td><td>12</td><td>15</td><td>18</td></tr> </table>	0	0	0	0	0	1	3	6	9	12	2	6	9	12	15	3	9	12	15	18	x1	0												
0	0	0	0	0																															
1	3	6	9	12																															
2	6	9	12	15																															
3	9	12	15	18																															
Haz. Waste Quantity	0 1 2 3 4 5 6 7 8	x1	0	Unknown	-																														
Total Waste Char. Score			0																																
5 Targets																																			
Surface Water Use	0 1 2 3	x3	0	Franklin Cr. Not currently used	8																														
Dist. to Sensitive Environment	0 1 2 3	x2	0	Now within 1 mile	7, 2																														
	Distance to Water Intake Downstream																																		
	<table style="font-size: small;"> <tr><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>0</td><td>4</td><td>6</td><td>8</td><td>10</td></tr> <tr><td>0</td><td>8</td><td>12</td><td>16</td><td>20</td></tr> <tr><td>0</td><td>12</td><td>16</td><td>24</td><td>30</td></tr> <tr><td>0</td><td>16</td><td>24</td><td>32</td><td>35</td></tr> <tr><td>0</td><td>20</td><td>30</td><td>35</td><td>40</td></tr> </table>	0	0	0	0	0	0	4	6	8	10	0	8	12	16	20	0	12	16	24	30	0	16	24	32	35	0	20	30	35	40			Surface water	
0	0	0	0	0																															
0	4	6	8	10																															
0	8	12	16	20																															
0	12	16	24	30																															
0	16	24	32	35																															
0	20	30	35	40																															
Population Served		x1	0	not used for drinking	8																														
Total Targets Score			0																																
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			0																																
7 Divide line 6 by 64,350 and multiply by 100			$S_{sw} = 0$																																

SURFACE WATER ROUTE

PROJECTED HRS SCORE WORKSHEET FOR SCREENING SITE INSPECTION (SS0)

(This score is based on the expected acquisition of information from the Screening Site Inspection.)

Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #
1 Observed Release	0 45	x1	0	No documentation	—
If Observed Release scores 45 proceed to line 4 If Observed Release scores 0 proceed to line 2					
2 Route Characteristics				Fact $\leq 3\%$	2
Intervening Terrain	0 0 0 0 3	x1	0	Interv $\leq 3\%$	2
Facility	0 1 1 2 3				
Slope	0 1 2 2 3				
	0 2 2 3 3				
	0 2 3 3 3				
1-yr. 24 hr Rainfall	0 1 2 3	x1	2	2.5 in.	5
Distance to Nearest Surface Water	0 1 2 3	x2	4	~1/4 mi to Franklin Cr.	2
Physical State	0 1 2 3	x1	3	Paint Sludges, Liquids	1
Total Route Char. Score			9		
3 Containment	0 1 2 3	x1	3	drums leaking	10
4 Waste Characteristics					
Persistence	0 1 2 3			Assume Heavy metals (lead) from Paint	
Toxicity	0 0 0 0 0 1 3 6 9 12 2 6 9 12 15 3 9 12 15 18	x1	18	Sludges	1
Haz. Waste Quantity	0 1 2 3 4 5 6 7 8	x1	5	~1400 Barrels	1,10
Total Waste Char. Score			23		
5 Targets					
Surface Water Use	0 1 2 3	x3	0	Franklin Cr. Not currently used	8
Dist. to Sensitive Environment	0 1 2 3	x2	0	None within 1 mile	7,2
Distance to Water Intake Downstream	0 0 0 0 0 0 4 6 8 10 0 8 12 16 20 0 12 18 24 30 0 16 24 32 35 0 20 30 35 40			Surface water	
Population Served		x1	0	Not used for drinking	8
Total Targets Score			0		
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			0		
7 Divide line 6 by 64,350 and multiply by 100			$S_{sw} = 0$		

SURFACE WATER ROUTE

PROJECTED HAS SCORE WORKSHEET FOR LISTING SITE INSPECTION (LSII)

(This score is based on the expected acquisition of information from the Listing Site Inspection.)

Rating Factor	Assigned Value (Circle One)	Multiplier	Score	Description	Ref. #																																
1 Observed Release	0 45	x1	0	No documentation	—																																
If Observed Release scores <5 proceed to line 4 If Observed Release scores 0 proceed to line 2																																					
2 Route Characteristics	Interpreting Terrain <table style="display: inline-table; vertical-align: top;"> <tr><td></td><td>0</td><td>0</td><td>0</td><td>0</td><td>3</td></tr> <tr><td>Facility</td><td>0</td><td>1</td><td>1</td><td>2</td><td>3</td></tr> <tr><td>Slope</td><td>0</td><td>1</td><td>2</td><td>2</td><td>3</td></tr> <tr><td></td><td>0</td><td>2</td><td>2</td><td>3</td><td>3</td></tr> <tr><td></td><td>0</td><td>2</td><td>3</td><td>3</td><td>3</td></tr> </table>				0	0	0	0	3	Facility	0	1	1	2	3	Slope	0	1	2	2	3		0	2	2	3	3		0	2	3	3	3	x1	0	Facility %	2
	0	0	0	0	3																																
Facility	0	1	1	2	3																																
Slope	0	1	2	2	3																																
	0	2	2	3	3																																
	0	2	3	3	3																																
				Inter %	2																																
1-yr. 24 hr. Rainfall	0 1 2 3	x1	2	2.5 in.	5																																
Distance to Nearest Surface Water	0 1 2 3	x2	4	~ 1/4 mile to Franklin	2																																
Physical State	0 1 2 3	x1	3	Paint Sludges, Liquids	1																																
Total Route Char. Score			9																																		
3 Containment	0 1 2 3	x1	3	drums leaking	10																																
4 Waste Characteristics	Persistence 0 1 2 3 Toxicity <table style="display: inline-table; vertical-align: top;"> <tr><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>1</td><td>3</td><td>6</td><td>9</td><td>12</td></tr> <tr><td>2</td><td>6</td><td>9</td><td>12</td><td>15</td></tr> <tr><td>3</td><td>9</td><td>12</td><td>15</td><td>18</td></tr> </table> Haz. Waste Quantity 0 1 2 3 4 5 6 7 8			0	0	0	0	0	1	3	6	9	12	2	6	9	12	15	3	9	12	15	18	x1	18	Assume Heavy metals (Lead) from Paint											
0	0	0	0	0																																	
1	3	6	9	12																																	
2	6	9	12	15																																	
3	9	12	15	18																																	
				Sludges	1																																
				~ 1400 Barrels	1																																
Total Waste Char. Score			23																																		
5 Targets	Surface Water Use 0 1 2 3 Dist. to Sensitive Environment 0 1 2 3 Distance to Water Intake Downstream <table style="display: inline-table; vertical-align: top;"> <tr><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>0</td><td>4</td><td>6</td><td>8</td><td>10</td></tr> <tr><td>0</td><td>8</td><td>12</td><td>16</td><td>20</td></tr> <tr><td>0</td><td>12</td><td>18</td><td>24</td><td>30</td></tr> <tr><td>0</td><td>16</td><td>24</td><td>32</td><td>35</td></tr> <tr><td>0</td><td>20</td><td>30</td><td>35</td><td>40</td></tr> </table> Population Served			0	0	0	0	0	0	4	6	8	10	0	8	12	16	20	0	12	18	24	30	0	16	24	32	35	0	20	30	35	40	x3	0	Franklin or Not currently used	8
0	0	0	0	0																																	
0	4	6	8	10																																	
0	8	12	16	20																																	
0	12	18	24	30																																	
0	16	24	32	35																																	
0	20	30	35	40																																	
				None within 1/2 mile	7, 2																																
				Surface water not used for drinking	8																																
Total Targets Score			0																																		
6 If line 1 is 45, multiply 1 x 4 x 5																																					
If line 1 is 0, multiply 2 x 3 x 4 x 5																																					
			0																																		
7 Divide line 6 by 64,350 and multiply by 100			S _{sw} = 0																																		

AIR ROUTE

PROJECTED HRS SCORE WORKSHEET FOR SCREENING SITE INSPECTION (SSD)

(This score is based on the expected acquisition of information from the Screening Site Inspection.)

Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #
1 Observed Release	<u>0</u> 45	x1	<u>0</u>	No documentation	✓
If line 1 is 0, the $S_a = 0$. Enter on line 5 If line 1 is 45, then proceed to line 2					
2 Waste Characteristics					
Reactivity & Incompatibility	0 1 2 3	x1			
Toxicity	0 1 2 3	x3			
Haz. Waste Quantity	0 1 2 3 4 5 6 7 8	x1			
Total Waste Char. Score					
3 Targets					
Population within 4-mile Radius Pop.		Dist to Population			
		0 0 0 0			
		9 12 15 18			
		12 15 18 21			
		15 18 21 24			
		18 21 24 27		x1	
		21 24 27 30			
Distance to Sensitive Environment	0 1 2 3	x2			
Land Use	0 1 2 3	x1			
Total Targets Score					
4 Multiply 1 x 2 x 3					
5 Divide line 4 by 35,100 and multiply by 100			$S_a = 0$		

AIR ROUTE

PRELIMINARY HRS SCORE WORKSHEET

(This score is based on existing file information that was obtained prior to the Screening Site Inspection.)

Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #
<input checked="" type="checkbox"/> Observed Release	<input checked="" type="radio"/> 0 45	x1	0	No documentation	—
If line 1 is 0, the $S_2 = 0$. Enter on line 5 If line 1 is 45, then proceed to line 2					
3 Waste Characteristics					
Reactivity & Incompatibility	0 1 2 3	x1			
Toxicity	0 1 2 3	x3			
Haz. Waste Quantity	0 1 2 3 4 5 6 7 8	x1			
Total Waste Char. Score					
3 Targets					
Dist to Population					
Population within 4-mile Radius					
Pop.	0 0 0 0				
	9 12 15 18				
	12 15 18 21				
	15 18 21 24				
	18 21 24 27	x1			
	21 24 27 30				
Distance to Sensitive Environment	0 1 2 3	x2			
Land Use	0 1 2 3	x1			
Total Targets Score					
4 Multiply 1 x 2 x 3					
5 Divide line 4 by 35,100 and multiply by 100					
			$S_2 = 0$		

AIR ROUTE

PROJECTED HRS SCORE WORKSHEET FOR LISTING SITE INSPECTION (LSI)

(This score is based on the expected acquisition of information from the Listing Site Inspection.)

Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #																								
[1] Observed Release	① 45	x1	0	No documentation	—																								
If line [1] is 0, the $S_a = 0$. Enter on line [5] If line [1] is 45, then proceed to line [2]																													
[2] Waste Characteristics																													
Reactivity & Incompatibility	0 1 2 3	x1																											
Toxicity	0 1 2 3	x3																											
Haz. Waste Quantity	0 1 2 3 4 5 6 7 8	x1																											
Total Waste Char. Score																													
[3] Targets	Dist to Population <table style="font-size: small;"> <tr><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>9</td><td>12</td><td>15</td><td>18</td></tr> <tr><td>12</td><td>15</td><td>18</td><td>21</td></tr> <tr><td>15</td><td>18</td><td>21</td><td>24</td></tr> <tr><td>18</td><td>21</td><td>24</td><td>27</td></tr> <tr><td>21</td><td>24</td><td>27</td><td>30</td></tr> </table>		0	0	0	0	9	12	15	18	12	15	18	21	15	18	21	24	18	21	24	27	21	24	27	30			
0	0	0	0																										
9	12	15	18																										
12	15	18	21																										
15	18	21	24																										
18	21	24	27																										
21	24	27	30																										
Population within 4-mile Radius	Pop	x1																											
Distance to Sensitive Environment	0 1 2 3	x2																											
Land Use	0 1 2 3	x1																											
Total Targets Score																													
[4] Multiply [1] x [2] x [3]			0																										
[5] Divide line [4] by 35,100 and multiply by 100			$S_a = 0$																										

FIRE AND EXPLOSION

PRELIMINARY HRS SCORE WORKSHEET

(This score is based on existing file information that was obtained prior to the Screening Site Inspection.)

Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #
1 Containment	<u>1</u> 3	x1	1	Barrels have been removed	1
2 Waste Characteristics					
Direct Evidence	<u>0</u> 3	x1	0	No documentation	-
Ignitability	<u>0</u> 1 2 3	x1	0	"	-
Reactivity	<u>0</u> 1 2 3	x1	0	"	-
Incompatibility	<u>0</u> 1 2 3	x1	0	"	-
Haz. Waste Quantity	<u>0</u> 1 2 3 4 5 6 7 8	x1	0	"	-
Total Waste Char. Score			0		
3 Targets					
Dist. to Nearest Pop.	0 1 2 <u>3</u> 4 5	x1	3	~ 500 FT	2
Dist. to Nearest Bldg.	0 1 2 <u>3</u>	x1	3	on site	9
Dist. to Sensitive Env.	<u>0</u> 1 2 3	x1	0	> 100 ft	2
Land Use	0 1 2 <u>3</u> . .	x1	3	Residential < 1/4 mile	2
Pop. Within 2 miles	0 1 2 <u>3</u> 4 5	x1	3	~ 1178 people	2.6
Bldgs. Within 2 miles	0 1 2 <u>3</u> 4 5	x1	3	~ 430 bldgs	2.6
Total Targets Score			15		
4 Multiply 1 x 2 x 3			75		
5 Divide line 4 by 1,440 and multiply by 100			S _{FE} =	0	

FIRE AND EXPLOSION

PROJECTED HRS SCORE WORKSHEET FOR SCREENING SITE INSPECTION (SSI)						
(This score is based on the expected acquisition of information from the Screening Site Inspection.)						
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #	
1 Containment	<u>1</u> 3	x1	1	Barrels have been removed	1	
2 Waste Characteristics						
Direct Evidence	<u>0</u> 1 2 3	x1	0	No documentation	-	
Ignitability	<u>0</u> 1 2 3	x1	0	Barrels, removed	-	
Reactivity	<u>0</u> 1 2 3	x1	0	"	-	
Incompatability	<u>0</u> 1 2 3	x1	0	"	-	
Haz. Waste Quantity	<u>0</u> 1 2 3 4 5 6 7 8	x1	0	"	-	
Total Waste Char. Score			0			
3 Targets						
Dist. to Nearest Pop.	0 1 2 <u>3</u> 4 5	x1	3	~500 ft	2	
Dist. to Nearest Bldg.	0 1 2 <u>3</u>	x1	3	on site	9	
Dist. to Sensitive Env.	<u>0</u> 1 2 3	x1	0	>100 ft	2	
Land Use	0 1 2 <u>3</u>	x1	3	Residential <1/4 mile	2	
Pop. Within 2 miles	0 1 2 <u>3</u> 4 5	x1	3	~1178 people	2.6	
Bldgs. Within 2 miles	0 1 2 <u>3</u> 4 5	x1	3	~430 bldgs	2.6	
Total Targets Score			15			
4 Multiply 1 x 2 x 3			75			
5 Divide line 4 by 1,440 and multiply by 100			S _{FE} = 0			

FIRE AND EXPLOSION

PROJECTED HRS SCORE WORKSHEET FOR LISTING SITE INSPECTION (LSI)

(This score is based on the expected acquisition of information from the Listing Site Inspection.)

Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #
1 Containment	1 3	x1	1	Barrels have been ^{removed}	1
2 Waste Characteristics					
Direct Evidence	0 3	x1	0	No documentation	-
Ignitability	0 1 2 3	x1	0	Barrels removed	1
Reactivity	0 1 2 3	x1	0	"	1
Incompatibility	0 1 2 3	x1	0	"	1
Haz. Waste Quantity	0 1 2 3 4 5 6 7 8	x1	0	"	1
Total Waste Char. Score			0		
3 Targets					
Dist. to Nearest Pop.	0 1 2 3 4 5	x1	3	~500 ft	2
Dist. to Nearest Bldg.	0 1 2 3	x1	3	on site	9
Dist. to Sensitive Env.	0 1 2 3	x1	0	>100 ft	2
Land Use	0 1 2 3	x1	3	Residential <1/4 mi	2
Pop. Within 2 miles	0 1 2 3 4 5	x1	3	~1178 people	2, b
Bldgs. Within 2 miles	0 1 2 3 4 5	x1	3	~430 bldgs	2, b
Total Targets Score			15		
4 Multiply 1 x 2 x 3			75		
5 Divide line 4 by 1,440 and multiply by 100			S _{FE} = 0		

DIRECT CONTACT

PRELIMINARY HRS SCORE WORKSHEET (This score is based on existing file information that was obtained prior to the Screening Site Inspection.)					
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #
1 Observed Incident	0 45	x1	0	No documentation	-
If line 1 is 45, proceed to line 4 If line 1 is 0, proceed to line 2					
2 Accessibility	0 1 2 3	x1	2	Area fenced	11
3 Containment	0 15	x1	0	Unknown	-
4 Waste Characteristics					
Toxicity	0 1 2 3	x5	0	Unknown	-
5 Targets					
Pop. Within 1 mile	0 1 2 3 4 5	x4	8	~ 1033 people	62
Dist. to Crit. Habitat	0 1 2 3	x4	0	None listed for Lee Co.	7
Total Targets Score			8		
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			0		
7 Divide line 6 by 21,600 and multiply by 100 $S_{DC} = 0$					

DIRECT CONTACT

PROJECTED HAS SCORE WORKSHEET FOR SCREENING SITE INSPECTION (SSU)					
(This score is based on the expected acquisition of information from the Screening Site Inspection)					
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #
[1] Observed Incident	0 45	x1	0	No documentation	—
If line [1] is 45, proceed to line [4] If line [1] is 0, proceed to line [2]					
[2] Accessibility	0 1 2 3	x1	2	Area fenced.	11
[3] Containment	0 15	x1	15	Assume No Containment	—
[4] Waste Characteristics					
Toxicity	0 1 2 3	x5	15	Assume Lead	—
[5] Targets					
Pop. Within 1 mile	0 1 2 3 4 5	x4	8	~1033 people	6.2
Dist. to Crit. Habitat	0 1 2 3	x4	0	None listed for Lee Co.	7
Total Targets Score			8		
[6] If line [1] is 45, multiply [1] x [4] x [5] If line [1] is 0, multiply [2] x [3] x [4] x [5]			3600		
[7] Divide line [6] by 21,600 and multiply by 100			S _{DC} = 16.67		

DIRECT CONTACT

PROJECTED HRS SCORE WORKSHEET FOR LISTING SITE INSPECTION (LSI)					
(This score is based on the expected acquisition of information from the Listing Site Inspection.)					
Rating Factor	Assigned Value (Circle One)	Multi-plier	Score	Description	Ref. #
1 Observed Incident:	0 45	x1	0	No documentation	—
If line 1 is 45, proceed to line 4 If line 1 is 0, proceed to line 2					
2 Accessibility	0 1 2 3	x1	2	Area fenced	11
3 Containment	0 15	x1	3	Assume No Containment	—
4 Waste Characteristics					
Toxicity	0 1 2 3	x5	15	Assume Lead	—
5 Targets					
Pop. Within 1 mile	0 1 2 3 4 5	x4	8	~ 1033 people	6, 2
Dist. to Crd. Haz. ar.	0 1 2 3	x4	0	Non-listed for Lead	7
Total Targets Score			8		
6 If line 1 is 45, multiply 1 x 4 x 5 If line 1 is 0, multiply 2 x 3 x 4 x 5			3600		
7 Divide line 6 by 21,600 and multiply by 100			S _{DC} = 16.67		

APPENDIX

Copies of the following addenda have been supplied to the U.S. Environmental Protection Agency and the appropriate state agencies. Refer to these addenda when reviewing this work plan.

Addendum

Title

A

**Routine Analytical Services
Contract Required Detection and
Quantitation Limits**

B

**Central Regional Laboratory
Detection Limits**

C

**Special Analytical Services Detection Limits
Drinking Water Samples**

D

**Special Analytical Services Detection Limits
High Concentration Samples**

REFERENCES

REFERENCE DOCUMENTATION SHEET

Ref.#	DESCRIPTION OF REFERENCE
1	U.S. EPA, May 22 1986, Potential Hazardous waste Site Preliminary Assessment, for Logan Storage Sites, U.S. EPA. ID: ILD025425914, Prepared by Kenneth Page, IEPA.
2	USGS, 1983, Grand Detour; 1983, Dixon East; 1983, Daysville; 1983, Franklin Grove; 1975, Chana; 1975, Ashton, Illinois Quadsamples, 7.5 minute Series: 1:24,000.
3	Illinois Dept. of Public Health, Well construction reports of 8 wells, Lee County, IL, T.21N, R.10E, sec's 1, 2, 3, 10, 11, 12.
4	U.S. Dept. of Commerce, 1979, National Climatic Center, Climatic Atlas of the United States, Ashville N.C.

REFERENCE DOCUMENTATION SHEET

Ref.#	DESCRIPTION OF REFERENCE
5	U.S. Dept. of Commerce, 1963, <u>Rainfall frequency atlas of the U.S.</u> , Technical Paper #40, Washington DC.
6	US Dept. of Commerce, 1982, Bureau of the Census, <u>Number of Inhabitants, Illinois, 1980 census.</u>
7	US Dept of Interior, 1989, US Fish + wildlife service <u>Endangered species list, Great lakes Region.</u>
8	Uphoff, Bill, January 30, 1990, City of Franklin Grove water dept., Telephone conversation, contacted by Jeff Taylor of E+E.

REFERENCE DOCUMENTATION SHEET

Ref.#	DESCRIPTION OF REFERENCE
9	<p>Illinois Environmental Protection Agency, May 29, 1980, memo to division files, site investigation by Amy Loiselle of IEPA.</p>
10	<p>Illinois Environmental Protection Agency, June 25, 1980, memo to division file on Logan storage, filed by Amy Loiselle of IEPA.</p>
11	<p>Illinois Environmental Protection Agency, January 21, 1981, observation report for Logan storage, filed by Amy Loiselle of IEPA.</p>
12	<p>Illinois Environmental Protection Agency, April 15, 1981 memo to division file on Logan storage, filed by LD LoPinto.</p>

SOURCES AND DATES OF INFORMATION COLLECTION

<u>SOURCE</u>	<u>DATE</u>
1) State Hazardous/Solid Waste Files	<u>1-17-90</u>
2) State Water Files	<u> </u>
3) State Air Files	<u> </u>
4) State Department of Health	<u> </u>
5) State Geological Survey	<u> </u>
6) State Department of Natural Resources	<u> </u>
7) State Fire Marshall	<u> </u>
8) County Department of Health	<u> </u>
9) County Engineer	<u> </u>
10) County Clerk/Recorder of Deeds	<u> </u>
11) City Department of Health	<u> </u>
12) City Engineer	<u> </u>
13) City Fire Department/Fire Marshall	<u> </u>
14) City Water/Sever Department	<u>Jan 30 1990</u>
15) U.S. Soil Conservation Service	<u> </u>
16) Others	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
STATE CONTACT(S): <u>Bob Wengow</u>	<u>815 982-7404</u>
(name)	(phone number)
<u> </u>	<u> </u>
(name)	(phone number)